



RADON CLOSED HOME PROTOCOLS

1. Closed housed conditions shall be maintained for 12 hours PRIOR to diagnostic testing for the most representative results.
2. ALL windows on every level of the building are to remain completely closed during the test.
3. Doors are opened only long enough to permit entry and exit.
4. Short Term test less than 4 days long should not be conducted during periods of severe storms or high winds(> 30mph).
5. Internal-external air exchange systems (other than furnace), such as whole house fan, window fans, fresh air setting on window air conditioner, bathroom vent fans, kitchen vent fans, microwave fans, clothes dryers should not be operated.
6. Fireplaces should be off and dampers closed.

Please contact Jeff @ Wisconsin Inspection Services & Consulting LLC with any questions or concerns. (608) 434-0790.